

Earl E. Preston Jr. Inc. & Whiteford Septic Service

Complete Septic System Service – One Call Does It All

Licensed & Insured in – Baltimore, Harford, Carroll, Cecil Counties & Maryland Home Improvement Commission

Authorized Jet Distributor



4045-C Federal Hill Road, Jarrettsville, MD 21084

Phone: 410-557-8100

Fax: 410-692-9530

Email: earljr@eprestonjr.com

www.eprestonjr.com

PROPOSAL

PROPOSAL SUBMITTED TO:

Mrs. Dillion, PR of Estate
1710 N. Fountain Green Rd
Bel Air, MD 21015

Date: September 16, 2020
Job: 1710 N. Fountain Green Rd
Realtor: Regina Crabb
Phone: 410-952-7070
Email: reginacrabb1@gmail.com

WE HEREBY SUBMIT SPECIFICATIONS AND ESTIMATES FOR: Installation of Holding Tanks
Per Home Land Environmental inspection report dated 6/20/2018.

Supply onsite sewage disposal permit.

Call Miss Utility.

Pump and abandon existing septic tank.

Connect to sewer line from house.

Install (2) 1,500-gallon concrete top-seam holding tanks complete with poly-loc risers to 6" above grade and high-level alarm to be installed in house.

Backfill all excavations grading disturbed areas smooth.

Price includes permit, materials, equipment and labor to complete quoted work.

\$7,450.00

Approximately one month after installation, Earl E. Preston Jr. Inc. will return to final grade and seed and mulch disturbed area.

\$750.00

Upon receipt of payment, if requested, supply inspection letter outlining septic repairs.

EXCLUSIONS: Rock excavation	Driveway damage/ repairs	Seed, sod, straw or mulch	Soil haul off
Irrigation location/damage/repairs	Dog fence damage	Utilities relocation/repair	Normal earth settlement repairs
Fence removal / replacement	Sediment control maintenance	Damage to trees	Ground water

**** When water tables are high and extremely wet ground conditions exist, grading of yards is almost impossible. E.E.P.Jr. Inc. will take all due care, but will not be responsible for ruts, tracks, or other ground damage caused by wet conditions. ****

We propose hereby to furnish material and labor, complete in accordance with above and only the above specifications, for the sum of: As shown above

Payment to be made as follows: Balance due upon Completion. Credit/debit card payments are subject to 3% surcharge.

A finance charge will be computed on any remaining balance. The monthly periodic rate is 1 ½ % of the balance, which is an annual percentage rate of 18%. In the event account is referred to an attorney for collection, customer will pay attorney's fees of 20%. All material is guaranteed to be as specified. All work to be completed in a workmanlike manner according to standard practices. Any alteration or deviation from above specification involving extra costs will become an extra charge over and above the estimate.

Contract is valid for a period of 30 days from the date above due to current economic conditions.

Acceptance of Proposal by Owner or Representative:

Signed: _____

Doug Dufour

Signed: _____

Printed: _____

Date: _____